

— LIGHTING THIS AREA IS DESIGNED BY THE LIGHTING CONSULTANT. REFER TO LIGHTING CONSULTANT DRAWING AND ARCHITECTURAL RCPS FOR EXACT FIXTURE QUANTITIES AND LOCATIONS.


REFER TO LIGHTING CONSULTANT'S DRAWINGS AND
ARCHITECTURAL RCPS FOR PUBLIC SPACE LIGHTING
LAYOUTS.

FOR PRICING PURPOSES, ASSUME THAT EACH UNIQUE FIXTURE TYPE WITHIN A SPACE SHALL ON A DEDICATED CONTROL ZONE (UNLESS OTHERWISE NOTED). PLUS ADDITIONAL ZONES FOR PRIMARY AND SECONDARY DAYLIGHT ZONES.

ASSUME EGRESS LIGHTING WITH BYPASS RELAYS FOR ALL LIGHTING IN THE PATH OF EGRESS.

GENERAL LIGHTING NOTES:

1. REFER TO DRAWING E0.00 FOR LEGEND, SYMBOLS AND GENERAL NOTES.
 2. REFER TO LIGHTING FIXTURE SCHEDULE ON DRAWING E7.30 SERIES FOR SPECIFICATION OF FIXTURES.
 3. REFER TO DRAWING E8.03 SERIES FOR LIGHTING CONTROL DRAWINGS.
 4. REFER TO ARCHITECTURAL FLOOR PLANS FOR EQUIPMENT LOCATIONS.
 5. REFER TO ARCHITECTS REFLECTED CEILING PLAN FOR EXACT LOCATION OF LIGHTING FIXTURE PRIOR TO INSTALLATION (TYPICAL).
 6. REFER TO ARCHITECTURAL ELEVATIONS FOR COORDINATION OF WALL MOUNTED FIXTURE LOCATIONS.
 7. LOCATION AND GROUPING ARRANGEMENT/ORIENTATION OF ALL SWITCHES SHALL BE COORDINATED WITH THE ARCHITECT, MECHANICAL EQUIPMENT, AND OTHER WALL-MOUNTED DEVICES PRIOR TO INSTALLATION.
 8. THE ELECTRICAL CONTRACTOR SHALL VERIFY ALL CEILING TYPES AND COORDINATE FIXTURE TRIMS PRIOR TO PURCHASE OF LIGHTING FIXTURES.
 9. THE ELECTRICAL CONTRACTOR SHALL FURNISH AND INSTALL ALL LIGHTING FIXTURES COMPLETE WITH MOUNTING HARDWARE.
 10. ALL EXIT SIGNS AND EMERGENCY EGRESS LIGHTING SHALL BE CONNECTED TO THE EMERGENCY GENERATOR.
 11. EMERGENCY EGRESS LIGHTING SHALL BE PROVIDED THROUGHOUT THE BUILDING TO ILLUMINATE ALL EGRESS CORRIDORS, LOBBIES, ETC. BRANCH CIRCUITS SHALL ORIGINATE FROM THE EMERGENCY GENERATOR. AREAS REQUIRING SUCH CONTROL OF EGRESS LIGHTING SHALL BE PROVIDED WITH BYPASS RELAYS. EMERGENCY BRANCH CIRCUIT CONDUCTORS ALL BE RUN IN SEPARATE DEDICATED CONDUITS WITH NO OTHER WIRING.
 12. UNDER NORMAL CONDITIONS, EMERGENCY LIGHTING SHALL FUNCTION LIKE THE NORMAL LIGHTING IN EACH SPACE. PROVIDE UL 924 LISTED DEVICE TO TURN EMERGENCY LIGHTS TO FULL BRIGHTNESS UPON LOSS OF NORMAL POWER, REGARDLESS OF CONTROL STATE.
 13. PROVIDE ALL REQUIRED MODULES, INTERFACES, NETWORK MANAGERS, AND CONTROL INTERCONNECTIONS AS REQUIRED BY THE MANUFACTURER(S) TO MEET THE SPECIFIED CONTROL INTENT.
 14. ALL LIGHTING FIXTURE LOCATIONS WITHIN A/V, IT, ELECTRICAL, AND MECHANICAL ROOMS SHALL BE COORDINATED WITH THE RESPECTING TRADES TO AVOID CONFLICTS WITH THE EQUIPMENT AND TO PROVIDE EVEN ILLUMINATION THROUGHOUT THE SPACE.
 15. COORDINATE THE LOCATION OF ALL EXIT SIGNS WITH INTERIOR SIGNAGE. INTERIOR SIGNAGE SHALL NOT BE OBSTRUCTED.
 16. FOR ELECTRIC PANEL LOCATIONS, REFER TO RESPECTIVE POWER FLOOR PLAN.
 17. EXIT SIGN DIRECTIONAL ARROWS SHALL BE AS INDICATED ON THE ELECTRICAL PLANS AND SHALL BE COORDINATED WITH THE ARCHITECTURAL PLANS AND REFLECTED CEILING PLANS.



KEY PLAN



LIGHTING THIS AREA IS DESIGNED BY THE LIGHTING CONSULTANT. REFER TO LIGHTING CONSULTANT DRAWING AND ARCHITECTURAL RCPS FOR EXACT FIXTURE QUANTITIES AND LOCATIONS.

LIGHTING RCP B - PARENT - LEVEL 1

$$\odot \quad 1/8" = 1'-0"$$

Seal	Date: OCTOBER 24, 2025
	Scale: 1/8" = 1'-0"
	Drawn By:
	Designed By:
	Checked By:
	Proj. Mgr.:
	Payette Job No.: 17480.00
	Cadd File:
	Client Job No.: J.170.24.4000
	Client Name:

These documents were prepared or
and that I am duly licensed

EL2.01B