REFER TO LIGHTING CONSULTANT'S DRAWINGS AND ARCHITECTURAL RCPS FOR PUBLIC SPACE LIGHTING LAYOUTS.

FOR PRICING PURPOSES, ASSUME THAT EACH UNIQUE FIXTURE TYPE WITHIN A SPACE SHALL ON A DEDICATED CONTROL ZONE (UNLESS OTHERWISE NOTED). PLUS ADDITIONAL ZONES FOR PRIMARY AND SECONDARY DAYLIGHT ZONES.

ASSUME EGRESS LIGHTING WITH BYPASS RELAYS FOR ALL LIGHTING IN THE PATH OF EGRESS.

KEYED NOTES:

1. REFER TO DRAWING E8.10 EGRESS STAIRWAY 2 AS TYPICAL.

GENERAL LIGHTING NOTES:

1. REFER TO DRAWING E0.00 FOR LEGEND, SYMBOLS AND GENERAL NOTES.
2. REFER TO LIGHTING FIXTURE SCHEDULE ON DRAWING E7.30 SERIES FOR SPECIFICATION OF FIXTURES.
3. REFER TO DRAWING E8.03 SERIES FOR LIGHTING CONTROL DRAWINGS.
4. REFER TO ARCHITECTURAL FLOOR PLANS FOR EQUIPMENT LOCATIONS.
5. REFER TO ARCHITECTS REFLECTED CEILING PLAN FOR EXACT LOCATION OF LIGHTING FIXTURE PRIOR TO INSTALLATION (TYPICAL).
6. REFER TO ARCHITECTURAL ELEVATIONS FOR COORDINATION OF WALL MOUNTED FIXTURE LOCATIONS.
7. LOCATION AND GROUPING ARRANGEMENT/ORIENTATION OF ALL SWITCHES SHALL BE COORDINATED WITH THE ARCHITECT, MECHANICAL EQUIPMENT, AND OTHER WALL-MOUNTED DEVICES PRIOR TO INSTALLATION.
8. THE ELECTRICAL CONTRACTOR SHALL VERIFY ALL CEILING TYPES AND COORDINATE FIXTURE TRIMS PRIOR TO PURCHASE OF LIGHTING FIXTURES.
9. THE ELECTRICAL CONTRACTOR SHALL FURNISH AND INSTALL ALL LIGHTING FIXTURES COMPLETE WITH MOUNTING HARDWARE.
10. ALL EXIT SIGNS AND EMERGENCY EGRESS LIGHTING SHALL BE CONNECTED TO THE EMERGENCY GENERATOR.
11. EMERGENCY EGRESS LIGHTING SHALL BE PROVIDED THROUGHOUT THE BUILDING TO ILLUMINATE ALL EGRESS CORRIDORS, LOBBIES, ETC. BRANCH CIRCUITS SHALL ORIGINATE FROM THE EMERGENCY GENERATOR. AREAS REQUIRING SUCH CONTROL OF EGRESS LIGHTING SHALL BE PROVIDED WITH BYPASS RELAYS. EMERGENCY BRANCH CIRCUIT CONDUCTORS ALL BE RUN IN SEPARATE DEDICATED CONDUITS WITH NO OTHER WIRING.
12. UNDER NORMAL CONDITIONS, EMERGENCY LIGHTING SHALL FUNCTION LIKE THE NORMAL LIGHTING IN EACH SPACE. PROVIDE UL 924 LISTED DEVICE TO TURN EMERGENCY LIGHTS TO FULL BRIGHTNESS UPON LOSS OF NORMAL POWER, REGARDLESS OF CONTROL STATE.
13. PROVIDE ALL REQUIRED MODULES, INTERFACES, NETWORK MANAGERS, AND CONTROL INTERCONNECTIONS AS REQUIRED BY THE MANUFACTURER(S) TO MEET THE SPECIFIED CONTROL INTENT.
14. ALL LIGHTING FIXTURE LOCATIONS WITHIN A/V, IT, ELECTRICAL, AND MECHANICAL ROOMS SHALL BE COORDINATED WITH THE RESPECTING TRADES TO AVOID CONFLICTS WITH THE EQUIPMENT AND TO PROVIDE EVEN ILLUMINATION THROUGHOUT THE SPACE.
15. COORDINATE THE LOCATION OF ALL EXIT SIGNS WITH INTERIOR SIGNAGE. INTERIOR SIGNAGE SHALL NOT BE OBSTRUCTED.
16. FOR ELECTRIC PANEL LOCATIONS, REFER TO RESPECTIVE POWER FLOOR PLAN.
17. EXIT SIGN DIRECTIONAL ARROWS SHALL BE AS INDICATED ON THE ELECTRICAL PLANS AND SHALL BE COORDINATED WITH THE ARCHITECTURAL PLANS AND REFLECTED CEILING PLANS.

1 LIGHTING RCP A - PARENT - LEVEL 0
1/8" = 1'-0"

NUMBER	DATE	DESCRIPTION
	10/24/25	ISSUED FOR CONSTRUCTION

KEY PLAN

ARCHITECT
PAYETTE ASSOCIATES, INC.
290 Congress Street, Fifth Floor
Boston, MA 02210
617.895.1000

ASSOCIATE ARCHITECT
KPN ARCHITECTS
1800 Washington Blvd, Suite 414
Baltimore, MD 21230
443.682.7757

CODE
CODE RED CONSULTANTS
154 Turnpike Road, Suite 200
Southborough, MA 01772
617.500.7633

CIVIL
RK&K
700 East Pratt Street, Suite 500
Baltimore, MD 21202
410.728.2900

LANDSCAPE ARCHITECT
OLIN
1617 John F. Kennedy Boulevard, Suite 1900
Philadelphia, PA 19103
215.440.0030

STRUCTURAL
COLUMBIA ENGINEERING, INC.
6210 Old Dobbin Lane, Suite 150
Baltimore, Maryland 21045
410.992.9970

VERTICAL TRANSPORTATION
ZIPF ASSOCIATES, INC.
25 Bala Avenue, Suite 201
Bala Cynwyd, PA 19004
610.667.1717

MEP
BR+A CONSULTING ENGINEERS
10 Guest Street, 4th Floor
Boston, MA 02135
617.254.0016

FIRE ALARM & FIRE PROTECTION
SETTY & ASSOCIATES
575 S. Charles Street, Suite 403
Baltimore, MD 21201
667.309.6036

AUDIO VISUAL & TELECOM
CONVERGENT TECHNOLOGIES DESIGN GROUP
6501 York Road
Baltimore, MD 21212
410.532.2395

SECURITY
THORNTON TOMASETTI
1330 Connecticut Ave, NW, Suite 300
Washington, DC 20036
202.580.6300

FOOD SERVICE
COLBURN GUYETTE
100 Ledgewood Place, Suite 104
Rockland, MA, 02370
781.826.5522

BUILDING ENCLOSURE
SIMPSON GUMPERTZ & HEGER
1625 Eye St NW
Suite 900
Washington, DC 20006
202.239.4199

LEED
SUSTAINABLE DESIGN CONSULTING
1432 K Street NW, 3rd Floor
Washington, DC 20005
202.667.1620

WIND & AIR QUALITY
RWDI
650 Woodland Rd.
W. Guelph, Ontario
Canada N1K 1B8
519.823.1311

VIBRATION & ACOUSTICS
COLIN GORDON ASSOCIATES
1350 Old Bayshore Hwy, Suite 799
Burlingame, CA 94010
415.570.0350

LIGHTING
FISHER MARANTZ STONE
22 West 19th Street, 6th Floor
New York, NY 10011
212.691.3020

SITE LIGHTING
TILLETT LIGHTING DESIGN ASSOCIATES
11 Hanover Square, 17th Floor
New York, NY 10005
212.766.0144

EMI/RFI (SHEILDING)
VITATECH ELECTROMAGNETICS
115 Juliad Ct., Suite 105
Fredericksburg, VA 22406
540.286.1984

CAMPUS UTILITIES
AEI AFFILIATED ENGINEERS
200 International Circle, Suite 5888
Hunt Valley, MD 21030
410.229.0090

LIFE SCIENCES BUILDING
600 N Broadway
Baltimore, MD 21205

JOHNS HOPKINS
UNIVERSITY
1800 Orleans St
Baltimore, Maryland 21287

LIGHTING RCP A - LEVEL 0

Seal

Professional Certification.

I certify that these documents were prepared or approved by me, and that I am duly licensed engineer under the laws of the State of Maryland.

Date:	OCTOBER 24, 2025
Scale:	1/8" = 1'-0"
Drawn By:	
Designed By:	
Checked By:	
Proj. Mgr.:	
Payette Job No.:	17480.00
Cadd File:	
Client Job No.:	J.170.24.4000
Client Dwg. No.:	

EL2.00A